MYSORE CITY IMPROVEMENT TRUST BOARD.

The 25th April 1905.

1. Notice is hereby given that sealed tenders will be received at the office of the Chairman up to 8th May 1905, for the construction of drains and other works in the Weavers' lines, Mysore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1905.

2. The plans, detailed estimate and conditions may be seen at the Chairman's office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the construction of drains and other works in the Weavers' Lines" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Board of Trustees, Mysore City Improvements, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of Drainage and other works to be done in Weavers' Lines or Block No. 94 of the 5th Drainage Area of the Mysore City.

No.	*Items of work.*	*Per.*	*Approximate Quantity.*
1	Earthwork excavation ordinary soil for constructing drains of Semi-peg top section.	C. yd.	404
2	Earthwork excavation for other soil for constructing drains of Semi-peg top section (average rate)	„	183
3	Machine ground surki mortar concrete for constructing drains of Semi-peg top section.	C. ft.	11,719
4	Machine ground surki mortar concrete for filling foundation of masonry works.	„	176
5	Burnt brick in machine ground surki mortar	„	538
6	Machine ground surki mortar plastering rendering smooth with cement.	Sqr.	202·31
7	Cement plastering	„	3·44
8	Coverings to drains at crossings with either armoured concrete or dressed 6" thick burnt stone slabs set in mortar.	S. ft.	1,114
9	Coping with dressed 3" thick burnt stone slabs set in mortar...	„	64
10	Lowering roads	L. S. Rupees.	
11	Removing and stacking rough stones	„	„

Machinery for grinding mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

D. SITARAM RAO, *Chairman.*

GOVERNMENT CENTRAL BOOK DEPOT.

Dated 28th April 1905.

The undermentioned Volumes of the Mysore Census Report and Tables for 1901 are available for sale at the Government Central Book Depot, Bangalore :—

	Rs.	a.	p.
Vol. No. I	5	0	0
Vol. No. II	4	0	0
Vol. No. III	4	0	0
Vol. No. IV	4	0	0
Talukwar Tables	1	0	0
Talukwar Statement of Caste and Creed	0	4	0
Village Population Tables	2	8	0

Notification dated 1st May 1905.

It is hereby notified for information that copies of Kannada Text for the Mysore Lower Secondary Examination of 1906 are available for sale.

The cost of the same is annas 3 a copy.

S. ABDUL HAI, *Curator.*